BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Maintenance of Strom Water Drains in Ward No.07

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. ABHISHEK M	
				In figures	In words
1	280.80	KSRRB M2100-5.1. Earth work excavation in marshy soil for foundation of structures as per drawing and technical specifications, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and filling back with approved material including cost of all materials, labour, HOM complete as per specifications. Manual Means upto 3 m depth	Cum	541.66	Rupees Five Hundred Forty One And Paise Sixty Six Only
2	1123.20	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	265.00	Rupees Two Hundred Sixty Five Only
3		GST @ 12%			

Executive Engineer
Project Division
Yelahanka Zone

Abhishek M
Contractor